



shetland
CONSTRUCTION & DEVELOPMENTS LTD

Fjakari, Ocraquoy, Cunningsburgh, Shetland ZE2 9HA
Tel Frank:07795964599 David:07795682885
e-mail: enquiries@scd-limited.co.uk
www.scd-limited.co.uk

**COMPONENT
SPECIFICATION
TIMBER FRAMED KIT
HOUSE**



sheffield

CONSTRUCTION & DEVELOPMENTS LTD

FOUNDATIONS

Block Clad Concrete strip foundations 600x150mm with block-work cavity wall [external walls] and 450x150mm with 150mm single skin block-work wall [internal support walls] construction to under-building.

Timber Clad Concrete strip foundation 600x150mm [external walls] and 450x150mm [internal support walls] with 150mm single skin block-work wall construction to under-building.

SOLUM

Hard-core blinded infill, polythene Damp Proof Membrane, 50mm concrete screed with ventilated air space under joists

GROUND FLOOR

D.P.C.	150mm PVC
Wallplate	38x139mm CLS treated
Joists	45x195mm treated regularised whitewood @ 400mm centres
Flooring	22mm thick Moisture Resistant T&G Chipboard flooring, glued and screwed.

EXTERNAL WALL PANELS

Runners	6"x2" CLS treated
Studs	6"x2" CLS treated at 600mm centres
Sheathing	9mm OSB
Firestops	38x50mm whitewood o/saw treated
Lintols	[3] No. 38x184mm CLS treated
Headbinder	6"x2" CLS treated
Fitch Beam	To Structural Engineer's specification.

EXTERNAL WALL CLADDING

Timber Clad	22x145mm whitewood treated scalloped boarding on 38x50mm whitewood o/saw treated battens, fixed with marine grade stainless steel nails.
Block Clad	100mm harled concrete block-work.

NON LOAD-BEARING INTERNAL PARTITIONS



sheffield

CONSTRUCTION & DEVELOPMENTS LTD

Runners 38x89mm CLS treated
Studs 38x89mm CLS treated @ 600mm centres

LOAD-BEARING INTERNAL PARTITIONS

Runners 38x89mm CLS treated
Studs 38x89mm CLS treated @ 400mm centres
Mid Dwangs 38x89mm CLS treated
Sheathing 9mm OSB nailed to one side only

FIRST FLOOR

Joists 45x195mm treated regularized whitewood @ 400mm centres, or engineered roof trusses at centres approved by Structural Engineer
Flooring 22mm thick Moisture Resistant T&G Chipboard flooring, glued and annular ring nailed.

ROOF

Trusses Generally 25/30 degree Fink Trusses or 40/45 degree Stub or Attic, TRADA designed
Wind Bracing 22x100mm whitewood, sawn treated.
Sarking 9mm OSB exterior grade sheathing.
Felt 22kg reinforced grade 1F or VP400 roofing membrane.
Counter Battens 12x38mm whitewood sawn treated.
Tile Battens 38x50mm whitewood sawn treated.
Roof Tiles Redland "Grovebury" precast concrete roof tiles c/w fixngs – colours Slate Grey, Tudor Brown or Terra Cotta [subject to Planning Consent]
Barge Board 22x170mm redwood dressed treated.
Fascia Board 22x230mm redwood dressed treated.
Soffit Board 9.5m Far Eastern Plywood, painted as required and fitted with colour matched PVC soffit vents.

WINDOWS

Scandinavian severe exposure rated laminated redwood windows. All double glazed with low emissive energy saving glass and Argon gas filled cavities, u-value 1.1 – 1.4 W/m²K.

ROOF WINDOWS

Velux [o.e.a.] severe exposure rated laminated redwood



sheffield

CONSTRUCTION & DEVELOPMENTS LTD

roof windows. All double glazed with low emissive energy saving glass and Argon gas filled cavities, u-value 1.4 – 1.5 W/m²K.

EXTERIOR DOORS

Front and/or Rear Locally manufactured hardwood door-sets with 3-point locking system, [4] stainless steel hinges and SAA furniture. All double glazed with low emissive energy saving glass.

Patio Doors NorDan laminated redwood pre-glazed sliding patio doors, where applicable. All double glazed with low emissive energy saving glass and Argon gas filled cavities, u-value 1. – 1.4 W/m²K.

INTERIOR DOORS

“Dooria” SKOG Oak veneered, pre-finished, hollow core door-sets complete with pre-finished door frames.

DOOR FURNITURE

“Karcher” [o.e.a.] stainless steel “designer range” furniture.

INSULATION

Loft/Roof Space 300mm glasswool insulation in [2] layer
External Walls 140mm glasswool insulation between studs with 25mm thick Kingspan [o.e.a.] rigid insulation over inside face of studs. 25x50mm whitewood sawn treated branderling fitted over to create a service void.
Bathroom 100mm glasswool insulation.
Under Floor 200mm glasswool insulation on 9.5mm OSB between joists, supported on 100mm wide x 9.5mm OSB strips, pinned to underside of joists.

Insulation specification may vary to satisfy specific SAP rating calculations

PLASTERBOARD

External Walls 12.5mm T/E Foil Backed [including garage]
Ceilings 12.5mm T/E Plain [single storey]
Ceilings 12.5mm T/E Fireline [multi storey]
Internal Partitions 12.5mm T/E Plain
Garage Ceiling 12.5mm T/E Fireline [integral garage]



sheffield

CONSTRUCTION & DEVELOPMENTS LTD

Toilets/Bathrooms 12.5mm T/E Moisture Resistant. [Walls]
Coving Plasterboard Coving to Lounge/Kitchen/
Dining Room.

STAIR Pre-fabricated staircase, softwood stringers and treads, MDF risers, Burbidge [o.e.a.] handrails and spindles, as required.

FINISHINGS Redwood facings, skirtings, cills, aprons and window ingoes.

SUNDRIES

Wardobes Chrome wardrobe hanging rails and fixings.
[1] full width MDF shelf

Loft Access [1] No. Fakro pre-fabricated, insulated loft access hatch c/w folding redwood ladder, or [1] No. Fakro pre-fabricated, insulated comb access door, as appropriate.

Cyl. Cupbd. [1] No. slatted shelf to provide dry linen storage

KITCHEN Choose, and design, your own kitchen using local or national Suppliers. A Prime Cost Sum is included in the kit price, which should be sufficient to fit out the house selected, however, you can increase, or decrease, your budget as required.

SANITARY WARE All as Kitchen/Utility.

CENTRAL HEATING Total Control Electric Heating system is fitted as standard. Oil Fired or Electric Boiler central heating, feeding a wet system of radiators, or under-floor heating, is available as an optional upgrade.

ELECTRICAL A standard number of sockets and light fittings, TV and telephone points are allowed for in accordance with current building standards. However, you can arrange the electrical layout, to suit your own requirements. Additional fittings requested will incur additional costs.

DECORATION Internal walls and ceilings will receive two coats of trade



shetland

CONSTRUCTION & DEVELOPMENTS LTD

emulsion paint [Magnolia to walls and White to ceilings]. All redwood finishings to receive three coats of clear varnish. External face of windows, fascias, barge boards and soffits to receive one coat primer and two coats Jotun Optimal. Colour to be confirmed. Recommend windows factory finished, one colour both sides. External painting of timber cladding boards is not included unless otherwise requested. [see separate paint spec.]

LANDSCAPING

The house site excavations are landscaped on completion of building works, using suitable excavated material, retained on site, only. Topsoil can be imported onto site, if required by Client, at an additional cost. Sufficient stone chip path, for access, has been allowed.

GENERAL DESIGN

All elements of our standard house kit construction meet with the requirements of the local authorities and the National House Building Council. We can provide Professional Supervision, together with a Six Year Warranty, on completion, if required.